



DHA SUFFA UNIVERSITY

DG -78, Off Khayaban-e-Tufail, Phase –VII (Extension), DHA, Karachi – 75500

Ph: 021-35244872
021-35244866
Fax: 021-35244856

In reply, please quote,
DHA/DSU/48/RFQ/008/2012-13

RFQ

Description : **Construction, Electrification & Commissioning of Lab**
Date of Issue : December 07, 2012
Date of Submission of Quotation : December 10, 2012
Date & Time of Opening : December 10, 2012 at 5:00 pm
Time of Completion : December 20, 2012
Contact Person & Telephone : Procurement Officer
021-35244872

S. #	Description
01	<p><u>Electrical Work / Power Cabling</u></p> <p>60 units of Light Points for Computer Tables with Clipsal Fitting / Fixtures</p> <p>12 units of Earth Point / Floor Points (06 for Networking and 06 for Electricity point)</p> <p>30 units of False Ceiling Light Points (False Ceiling Points with PVC Pipe wiring including Earth wiring points)</p> <p>Cable work Single Phase 07/64 with 2.5mm Earth wire. From Electrical Room to Lab. Wiring with Adamjee Dura Duct.</p>
02	<p><u>Glass Work</u></p> <p>Construction of False Beam Size 8' x 8' x 2'</p> <p>Glass Cabin size 8' x 8' x 8' 02 Walls, 12mm tempered Glass.</p> <p>Glass Door size 7' x 4' (02 Panels with Floor Mounted Door stopper) lock, hinges and Handle.</p> <p>02" sand Blasting Strip</p>
03	<p><u>Wall Paneling</u></p> <p>Wood Paneling size 35' x 30" = 02 walls</p> <p>Wood Paneling size 25' x 30" = 02 walls</p> <p>Wooden Frame work with Lasani Sheet ½ with Paint or Polish finish. (as per approved design and texture)</p>
04	<p><u>False Ceiling Work</u></p> <p>False Ceiling Work size 35' x 25' with Gypsum 2' x 2'</p> <p>CKM Brand with channel patti or equivalent</p> <p>As per approved design and texture)</p> <p>False Ceiling Concealed Lights with 02 Energy Savers</p> <p>As per requirement</p>

05	<u>Paint Work</u> Distemper Paint Ash White Room size 35' x 10' = 02 Wall 25' x 10' = 02 Wall
06	<u>Floor Tiles and Dismantling of Floor</u> Dismantling of Floor Size: 25' x 6' 35' x 3' 35' x 3' 35' x 2' Providing / Fixing of EMCO Ceramic Floor Tiles 12" x 12" 430 sqft with skirting 120 Rft.
07	<u>Window Blinds:</u> Window Blinds Size 76" x 78" 03 units 4" Vertical Window Repairing / Water Proofing of 03 Windows
08	<u>Door Work</u> Dismantling of 02 units of Door Frames, Providing, Supply and Fixation of new Doors with Frames as per sample
09	<u>Provide, Supply and Fixation of Sliding and Fixed White Board</u> Sliding Magnetic White Board size 14' x 4' 01 unit of Fixed White Board for Multimedia 6' x 6'

Terms & Conditions:

- 1- We reserve the right to cancel any or all the above items if material is not in accordance with our specification or if the delivery is delayed.
- 2- Payment will be made through crossed cheque after the receipt of the bill and delivery of the above items.
- 3- General Sales Tax will be applied on applicable items only.
- 4- Penalty at the rate of 2% per month on actual will be imposed on delayed delivery.
- 5- The rate / item cost is final and no change what so ever will be accepted.
- 6- Competent Authority reserves the right to change / alter / remove any item or article or reduce / enhance quantity upto 15% without assigning any reason.
- 7- Invoice / bill & Delivery Challan should be submitted to the Procurement Officer.
- 8- No subletting in any case / item / form will be allowed.
- 9- Sample(s) and image(s) are available at the Procurement Office and can be seen during office hours for ready reference.

Procurement Officer